

Datenblatt für Artikel: SR3PDIPP08

PDU PRO Metered+, 24xCombo (C13, C15, C19, C21), 400V, 32A, RCM

Metering per outlet, Residual Current Monitoring per phase, incl. mounting bracket with screws



SCHRACK-Info

- PDU PRO Metered+ inkl. RCM
- Metering per socket
- Residual Current Monitoring per phase, Typ B
- Input: 32 A / 400 V | 22 kW
- Supply cable: 3,0 m | 4 mm²
- with CEE plug 32 A red
- Output: 24x Combo C13/C15/C19/C21
- 6x hydraulic-magnetic circuit breakers 16 A
- Integrierte Funktion zur Messung von Strom, Spannung, Blind-, Schein-, Wirkleistung, Blind-, Schein-, Wirkenergie, Frequenz und Leistungsfaktor
- Im Betrieb tauschbarer Controller und tauschbares Netzteil
- Integrated function for measuring current, voltage, reactive, apparent and active power, Reactive, apparent and active energy, frequency and power factor
- Hot-swappable controller and power supply unit
- Integrated web server with web interface 1x Gbit/s (PoE) and 1x 10/100Mbit/s Ethernet connection
- Interface for PDU network (up to 20 PDUs)
- 1x RJ45 interface for up to ten external sensors

- 1 x USB-C port (USB 2.0)
- 2.4" TFT color display
- Incl. frames for color coding (blue, red)
- Incl. mounting brackets (L-shaped) </l

Technische Daten

Netto lengte (mm)	1.838,70
Breedte (mm)	56,00
Hoogte (mm)	71,00
EAN CODE	4057298230448
PRIJS	6.940,00
Omgevingstemperatuur min. (°C)	0
Omgevingstemperatuur max. (°C)	50
Nominale spanning	400V
Beschermingsgraad	IP20
Type product	Metered+
Aantal stopcontacten	24
Type connector	24 x Combo Socket (C13/C15/C19/C21)
Nominale stroom (A)	32
Fasen per voeding	3
Aansluittype	CEE 32 A rood
Protocol	LDAP IPv6 IPv4 DNS SNMPv1 SSH HTTP SNMPv3 SNMPv2 NTP SSH2 DHCP ModBus /TCP SMTP HTTPS SNMP Trap Syslog
Bevestiging	Bevestigingshoek (L-vormig)

BEZEICHNUNG	BEST.NR.
PDU PRO Metered+, 24xCombo (C13, C15, C19, C21), 400V, 32A, RCM Metering per outlet, Residual Current Monitoring per phase, incl. mounting bracket with screws	SR3PDIPP08