

Datenblatt für Artikel: SR3PDIPS04

PDU PRO Switched, 36xCombo (C13,C15,C19,C21), 400V, 16A, RCM

Measurement per phase (measurement at socket level can be upgraded with license), Residual Current Monitoring per phase, switchable per socket, includes mounting bracket with screws



SCHRACK-Info

- PDU PRO Switched RCM
- Metering per phase
- Can be upgraded to measuring per socket at any time via licence (SR3PAB0011,SR3PAB0012,SR3PAB0013)
- Residual Current Monitoring per phase, Typ B
- switchable sockets
- Input: 16 A / 400 V | 11 kW
- Supply cable: 3,0 m | 2,5 mm²
- with CEE plug 16 A red
- Output: 36x Combo C13/C15/C19/C21
- Integrated function for measuring current, voltage, reactive, apparent and active power, Reactive, apparent and active energy, frequency and power factor
- Hot-swappable controller and power supply unit
- Integrated web server with web interface 1x Gbit/s (PoE) and 1x 10/100Mbit/s Ethernet connection
- Interface for PDU network (up to 20 PDUs)
- 1x RJ45 interface for up to ten external sensors
- 1x USB-C port (USB 2.0)
- 2.4" TFT color display

- Incl. frames for color coding (blue, red)
- Incl. mounting brackets (L-shaped) </l

Technische Daten

Netto lengte (mm)	1.696,50
Breedte (mm)	56,00
Hoogte (mm)	71,00
EAN CODE	4057298230530
PRIJS	7.178,00
Omgevingstemperatuur min. (°C)	0
Omgevingstemperatuur max. (°C)	50
Nominale spanning	400V
Beschermingsgraad	IP20
Type product	Switched
Aantal stopcontacten	36
Type connector	36 x Combo Socket (C13/C15/C19/C21)
Nominale stroom (A)	16
Fasen per voeding	3
Aansluittype	CEE 16 A rood
Protocol	LDAP IPv6 IPv4 DNS SNMPv1 SSH HTTP SNMPv3 SNMPv2 NTP SSH2 DHCP ModBus /TCP SMTP HTTPS SNMP Trap Syslog
Bevestiging	Bevestigingshoek (L-vormig)

BEZEICHNUNG	BEST.NR.
PDU PRO Switched, 36xCombo (C13,C15,C19,C21), 400V, 16A, RCM Measurement per phase (measurement at socket level can be upgraded with license), Residual Current Monitoring per phase, switchable per socket, includes mounting bracket with screws	SR3PDIPS04